

Assembly Bill of Quantity

Client Details

Job Details

Job ID: <input style="width: 100%;" type="text"/>

Tuesday, 28 August 2007

Printed: 10:13:52 AM

Page 1 of 1

Selected Assembly

Assembly ID	Quantity	Description	Unit	Rate	Total
0002510	50.00	Int/Wall 2.400h 70X35 F5 450mm Crs	Met	\$102.14	\$5,107.21

Assembly Quantity List

Carpenter Labour

Description	Quantity	Unit	Rate	Ex/GST	GST	Cost
Carpenter - Frame Internal Walls	30.30	Met	\$35.00	\$964.09	\$96.41	\$1,060.50
Total for: Carpenter Labour				\$964.09	\$96.41	\$1,060.50

Frame Hardware

Description	Quantity	Unit	Rate	Ex/GST	GST	Cost
Masonry Nails 75mm	1.00	No	\$9.07	\$8.25	\$0.82	\$9.07
Connector Plates	1.00	No	\$29.77	\$27.06	\$2.71	\$29.77
Total for: Frame Hardware				\$35.31	\$3.53	\$38.84

Timber Wall Frame and Trusses

Description	Quantity	Unit	Rate	Ex/GST	GST	Cost
70x35 F5 Radiata	459.00	Met	\$2.23	\$930.52	\$93.05	\$1,023.57
Total for: Timber Wall Frame and Trusses				\$930.52	\$93.05	\$1,023.57

Mouldings

Description	Quantity	Unit	Rate	Ex/GST	GST	Cost
68x12 Colonial Skirting	105.30	Met	\$2.09	\$200.07	\$20.01	\$220.08
Total for: Mouldings				\$200.07	\$20.01	\$220.08

Plasterboard and Linings

Description	Quantity	Unit	Rate	Ex/GST	GST	Cost
10mm Plasterboard Walls Fixed	252.00	m2	\$9.20	\$2,107.64	\$210.76	\$2,318.40
90mm Plasterboard Cornice	105.00	Met	\$4.36	\$416.18	\$41.62	\$457.80
Total for: Plasterboard and Linings				\$2,523.82	\$252.38	\$2,776.20

Assembly Costed Total:	Cost Ex/GST	Estimate GST	Cost Inc/GST
	\$4,653.81	\$465.38	5,119.19